



- TOTAL CONTAINMENT**
- New Cell #4 must be constructed;
  - All in-coming wastewater flows are held on site;
  - Disposal is accomplished by evaporation only;
  - Large size is required to hold all possible flows;
  - Low-power mixing added to enhance evaporation;
  - Very low power required;
  - Very low maintenance;
  - Higher capital cost.
- CONSTRUCTION COST:**  
\$1,156,000
- PRESENT WORTH:**  
\$2,328,000

TOTAL CONTAINMENT  
ALTERNATIVE  
N.T.S.